

CORNER NOTES

A Found a 3/4" aluminum monument in a mound of stone in a N/S fenceline (CS 751).

Fd. steel fence post with BT tag North 5.2 ft.
Fd. steel fence post with BT tag East 4.6 ft.
Fd. steel fence post with BT tag South 3.8 ft.
Fd. steel fence post with BT tag West 4.6 ft.

B Found a 3/4" aluminum monument in a N/S fenceline (CS 751).
13" Ponderosa Pine S430°E, 46.0 ft, scribed W1/16S24BT, with washer "PLS 848".
13" Ponderosa Pine N22°0'E, 63.0 ft, scribed W1/16S13BT, with washer "PLS 848".

C Found a 2" brass cap on iron pipe in a mound of stone.
31" Ponderosa Pine, original, S20°W, 28.9 ft (rec S40°W, 42 lks), scribed 1/4S in opened face.
28" Ponderosa Pine, original, N53°E, 36.7 ft (rec N40°E, 54 lks), scribed 1/4S in opened face.
9" Ponderosa Pine S12°0'W, 87.4 ft, scribed 1/4BT.
13" Ponderosa Pine N7°0'W, 59.8 ft, scribed 1/4SBT.

D Found a 3/4" aluminum monument (CS 751).
Fd. steel fence post with BT tag North 3.2 ft.
Fd. steel fence post with BT tag South 4.3 ft.

E Set a 3/4"x30" aluminum monument 23" in the ground in a mound of stone.
Set a 2" aluminum cap on 3/4"x30" rebar North 10.0 ft, stamped RM CW1/16 S24 SOUTH 10.0 PLS1918 1985.
Set a 2" aluminum cap on 3/4"x30" rebar South 10.0 ft, stamped RM CW1/16 S24 NORTH 10.0 PLS1918 1985.

F Set a 3/4"x30" aluminum monument 12" in the ground in a mound of stone.
Marked a 10" Ponderosa Pine N84°0'W, 44.9 ft, scribed C1/4S24BT, with washer "LS 1918".
Marked an 11" Ponderosa Pine S13-3/40W, 49.5 ft, scribed C1/4S24XBT, with washer "LS 1918".

G Found a 17x16x5 stone (rec 16x16x10) marked 1/4 on the under (west) side. Set a 3/4"x30" aluminum monument 18" in the ground in a mound of stone. Placed the original stone in the mound.
38" Ponderosa Pine, original, S63°0'W, 62.4 ft (rec S62°0'W, 93 lks), scribed 1/4S in opened face.
29" Ponderosa Pine, original, N64°0'E, 27.1 ft, (rec N63°E, 28 lks), scribed 1/4S in opened face.
Marked a 5" Ponderosa Pine S33-3/40W, 45.1 ft, scribed 1/4S24BT, with washer "LS 1918".
Marked a 10" Fir N68°0'W, 70.4 ft, scribed 1/4S24BT, with washer "LS 1918".

H Set a 3/4"x30" aluminum monument 22" in the ground in a mound of stone.
Set a 2" aluminum cap on 3/4"x30" rebar North 10.0 ft, stamped RM SW1/16 S24 SOUTH 10.0 PLS1918 1985.
Set a 2" aluminum cap on 3/4"x30" rebar East 10.0 ft, stamped RM SW1/16 S24 WEST 10.0 PLS1918 1985.

I Set a 3/4"x30" aluminum monument 10" in the ground in a mound of stone.
Marked a 12" Ponderosa Pine S36-3/40W, 32.8 ft, scribed CS1/16S24BT, with washer "LS 1918".
Marked a 7" Ponderosa Pine S55°0'E, 61.6 ft, scribed CS1/16S24BT, with washer "LS 1918".

J Found a 3/4" aluminum monument in a mound of stone at a fence intersection (CS 751).
Fd. steel fence post with BT tag North 24.8 ft.
Fd. steel fence post with BT tag West 17.2 ft.
Fd. steel fence post with BT tag East 7.7 ft.
Fd. steel fence post with BT tag South 6.4 ft.

T16S R334E
S14S13

S23S24
1982
PLS 848

T16S R334E
S13
W1/16-----
S24
1982
PLS 848

GRANT CO SURV
1/4
13

24
1969
LS 848

T16S R334E
1/4
S23S24
1982
PLS 848

T16S R334E
W1/16
C-----C
S24
PLS 1918
1985

T16S R334E
C1/4
+
S24
PLS 1918
1985

T16S
R334E
1/4
S24
PLS 1918
1985

T16S R334E
SW1/16
+
S24
PLS 1918
1985

T16S R334E
C
S1/16S24
C
PLS 1918
1985

T16S R334E
S23S24

S26S25
1982
PLS 848

K Found no evidence of the original monument or accessories.
Reset this corner by single proportion. Set a 3/4"x30" aluminum monument 22" in the ground in a mound of stone, in a N/S fenceline.
Marked a 10" Ponderosa Pine N58°0'E, 225.7 ft, scribed 1/4S24BT, with washer "LS 1918".
Marked a 9" Ponderosa Pine S11-3/40E, 219.5 ft, scribed 1/4S25BT, with washer "LS 1918".

T16S R334E
S24
1/4---
S25
PLS 1918
1985

L Found a 16x12x7 stone (rec 24x14x5), 2 notches on the South side, 4 notches on the North side, lying top to East. Set a 3/4"x30" aluminum monument 12" in the ground in a mound of stone. Placed the original stone in the mound.
18" Ponderosa Pine, original, S31°0'W, 51.6 ft, (rec S30°0'W, 78 lks) scribed T16SR334ES25BT in opened face.
23" Fir N19°0'W, 31.8 ft, (rec Pine N18°0'W, 46 lks), scribed 334ES24BT in opened face.
Marked a 7" Ponderosa Pine N78°0'E, 33.1 ft, scribed T16SR34ES19BT, with washer "LS 1918".
Marked an 11" Fir S29°0'W, 28.0 ft, scribed T16SR334ES25BT, with washer "LS 1918".
Marked a 7" Ponderosa Pine N28-3/40W, 119.1 ft, scribed T16SR334ES24BT, with washer "LS 1918".
Note: Two trees, a 6' high stump with fragmentary scribing and chaining notch, and a 1' high stump with chaining notch lie South approximately 250 feet from this corner. I believe that these were set in error and defaced by Cooke.

T16S
R334E R34E
S24
-----S19
S25
PLS 1918
1985

M Found no evidence of the original monument or accessories.
Reset this corner by single proportion. Set a 3/4"x30" aluminum monument 20" in the ground in a mound of stone.
Set a 2" aluminum cap on 3/4"x30" rebar West 10.0 ft, stamped RM 1/4 S26 EAST 10.0 PLS1918 1985.
Set a 2" aluminum cap on 3/4"x30" rebar S30°E, 10.0 ft, stamped RM 1/4 S25 N30W 10.0 PLS1918 1985.

T16S R334E
1/4
S26S25
PLS 1918
1985

N Set a 3/4"x30" aluminum monument 27" in the ground.
Set a 2" aluminum cap on 3/4"x30" rebar North 10.0 ft, stamped RM C1/4 S25 SOUTH 10.0 PLS1918 1985.
Set a 2" aluminum cap on 3/4"x30" rebar South 10.0 ft, stamped RM C1/4 S25 NORTH 10.0 PLS1918 1985.

T16S R334E
C1/4
+
S25
PLS 1918
1985

O Found a 16x12x8 stone (rec 18x18x12), firmly set, 1/4 on the west face. Set a 3/4"x30" aluminum monument 15" in the ground in a mound of stone and placed the original stone in the mound.
32" Ponderosa Pine, original, N11-3/40W, 28.0 ft (rec N8°0'W, 41 lks), scribed 1/4S in opened face.
22" Ponderosa Pine, original, S2-3/40E, 44.0 ft (rec S5°E, 64 lks), healed scar.
Marked an 8" Ponderosa Pine N64-3/40W, 27.2 ft, scribed 1/4S25BT, with washer "LS 1918".
Marked an 8" Fir S36°0'W, 16.5 ft, scribed 1/4S25BT, with washer "LS 1918".
Note: approximately 250 feet south of this corner, I found a large Ponderosa Pine, blazed and with a chaining notch, on scribing visible. See the note for corner "L" above.

T16S
R334E
1/4
S25
PLS 1918
1985

P Set a 3/4"x30" aluminum monument 14" in the ground in a mound of stone.
Marked an 8" Ponderosa Pine S62°0'W, 15.1 ft, scribed SW1/16S25BT, with washer "LS 1918".
Marked a 10" Ponderosa Pine N28-3/40W, 15.8 ft, scribed SW1/16S25BT, with washer "LS 1918".

T16S R334E
SW 1/16
+
S25
PLS 1918
1985

Q Set a 3/4"x30" aluminum monument 18" in the ground in a mound of stone.
Marked a 13" Lodgepole Pine S89-3/40E, 37.9 ft, scribed CS1/16S25BT, with washer "LS 1918".
Marked a 9" Ponderosa Pine S35°0'W, 145.3 ft, scribed CS1/16S25BT, with washer "LS 1918".

T16S R334E
C
S1/16S25
C
PLS 1918
1985

R Found 18x9x9 stone (record 16x14x12), 1 notch in the east side, 1 notch in the south side, leaning to the Northwest, in a small mound of stone. Set a 3/4"x30" aluminum monument 22" in the ground in a mound of stone and placed the original stone in the mound.
Set a 2" aluminum cap on 3/4"x30" rebar S50°W, 15.8 ft, stamped T16S R334E RM S35 N50E 15.8 PLS1918 1985.
Set a 2" aluminum cap on 3/4"x30" rebar N44°0'W, 15.3 ft, stamped T16S R334E RM S26 S44E 15.3 PLS1918 1985.
Marked a 12" Ponderosa Pine N70°E, 282.5 ft, scribed T16SR334ES25BT, with washer "LS 1918".
Marked an 8" Ponderosa Pine S23-3/40E, 276.0 ft, scribed T16SR334ES36BT, with washer "LS 1918".

T16S R334E
S26S25

S35S36
PLS 1918
1985

S Set a 3/4"x30" aluminum monument 22" in the ground in a mound of stone.
Marked a 7" Ponderosa Pine N34°0'E, 17.3 ft, scribed W1/16S25BT, with washer "LS 1918".
Marked an 8" Ponderosa Pine S25°0'E, 10.5 ft, scribed W1/16S36BT, with washer "LS 1918".

T16S R334E
S25
W1/16---
S36
PLS 1918
1985

RECORD OF SURVEY for the U. S. FOREST SERVICE

MALHEUR NATIONAL FOREST
Secs. 24, 25, and 36, T 16 S, R 33-1/2 E, W.M.
and the NE1/4, Sec. 1, T 17 S, R 33-1/2 E, W.M.
Grant County, Oregon
Road Cadastral Survey
5 July 1985

T Found a 16x14x10 stone (rec 18x16x14) firmly set, no marks visible, in approximately correct relationship to original bearing trees. Set a 3/4"x30" aluminum monument 20" in the ground in a mound of stone and placed the original stone in the mound.
A Pine, original, down and deteriorating, S46°0'E, 9.2 ft (rec S53°E 13 lks), BT and chaining notch visible.
A Pine, original, down and deteriorating, N46°0'E, 12.9 ft (rec N42°E, 16 lks) BT and chaining notch visible.
Marked a 6" Lodgepole Pine N36°0'W, 12.6 ft, scribed 1/4S25BT, with washer "LS 1918".
Marked an 11" Ponderosa Pine S84°0'W, 25.0 ft, scribed 1/4S36BT, with washer "LS 1918".

T16S R334E
S25
1/4 ---
S36
PLS 1918
1985

U Found no evidence of the original corner monument. Reset the corner from the one remaining original bearing tree. The corner position falls approximately 1" Southwest of a 16" Ponderosa Pine. To mark the corner location, I set a 3/8" spike in the tree, 2" above the ground, with the head of the spike at the corner, and set a washer marked "LS 1918" in a blaze immediately above the spike.
A Pine, original, down and deteriorating, S45°0'W, 38.3 ft (record) to the estimated standing position of the face.
Set a 2" aluminum cap on a 3/4"x30" rebar S53°0'W, 2.3 ft, stamped T16S R334E RM S36 N53E 2.3 PLS1918 1985.
Marked a 12" Ponderosa Pine S63°0'E, 11.4 ft, scribed T16SR34ES30BT, with washer "LS 1918".
Marked an 11" Ponderosa Pine N59°0'W, 22.8 ft, scribed T16SR334ES25BT, with washer "LS 1918".
Marked a 7" Ponderosa Pine S24-3/40W, 49.8 ft, scribed T16SR334ES36BT, with washer "LS 1918".
Note: approximately 250 feet South of this corner I found a pine, blazed and with chaining notch but no visible scribing. See note for corner "L" above.

V Found a 16x9x7 stone (rec 20x18x12), firmly set, with 1/4 on the west face. Set a 3/4"x30" aluminum monument 12" in the ground in a mound of stone, in a N/S fenceline. Placed the original stone in the mound.
A Pine, original, down and deteriorating, N62°0'W, 29.7 ft (rec N62°0'W, 43 lks), scribed 1/4SBT.
18" Pine stump N82°0'E, 41.1 ft (rec S88°E 62 lks), scar and chaining notch visible.
Marked a 7" Ponderosa Pine N58°0'W, 40.1 ft, scribed 1/4S36BT, with washer "LS 1918".
Marked a 7" Ponderosa Pine S24°0'W, 51.2 ft, scribed 1/4S36XBT, with washer "LS 1918".

T16S
R334E
1/4
S36
PLS 1918
1985

W Found no evidence of the original monument. Reset the corner at the east edge of a large mound of earth and stone which I believe to be an accessory to the original corner. Corner falls approximately 1.5 ft South of a fence corner. Set a 3/4"x30" aluminum monument 22" in the ground in a mound of stone.
Set a 2" aluminum cap on 3/4"x30" rebar S52°0'W, 14.8 ft, stamped RM T17S R334E S1 N52E 14.8 PLS1918 1985.
Set a 2" aluminum cap on 3/4"x30" rebar N44°0'W, 23.2 ft, stamped RM T16S R334E S36 S44E 23.2 PLS1918 1985.
Marked a 12" Ponderosa Pine S45-3/40E, 213.2 ft, scribed T16SR34ES31BT, with washer "LS 1918".

T16S
R334E R34E
S36
-----S31
S 11
T17S
PLS 1918
1985

X Found a 16x8x7 stone (rec 16x16x5) with a distinct 1/, and an indistinct 4, on the west side, in a small ring of stones and with a mound of stone to the West. Set a 3/4"x30" aluminum monument 18" in the ground in a mound of stone. Placed the original stone in the mound.
Marked a 13" Ponderosa Pine S58°0'W, 160.6 ft, scribed 1/4S1BT, with washer "LS 1918".
Marked a 12" Ponderosa Pine N56-3/40W, 130.9 ft, scribed 1/4S1BT, with washer "LS 1918".

T17S
R334E
1/4
S 11
PLS 1918
1985

TYLER B. PARSONS
1915 SE STONE STREET
CORVALLIS, OR 97333
(503) 752-7515

REGISTERED
PROFESSIONAL
LAND SURVEYOR

TYLER B. PARSONS
JULY 18, 1980
1918

RECEIVED AND
FILED

AUG 22 1985

OFFICE OF COUNTY SURVEYOR

Attest: *Carol Duff C. Clark*

Sheet 2 of 2

MAP OF SURVEY NO. 885