



RIGHT-OF-WAY LIMITS, GRANT COUNTY ROAD NO. 21  
30 FT EACH SIDE OF CENTERLINE  
(SEE BOOK OF DEEDS NO. 87, PAGE 103.)

De: 20° E

SCALE  
0 20 40 60 80 100

BEARINGS ARE BASED UPON THE RECORD BEARING OF THE LINE BETWEEN THE CENTER EAST 1/16 CORNER AND THE SOUTHEAST 1/16 CORNER AS SHOWN ON PLAT OF SURVEY BY BISHOP, PLS 896, DATED DECEMBER 20, 1980.

CENTERLINE DATA - GRANT COUNTY ROAD NO. 21 AS CONSTRUCTED								
CURVE NO.	CENTERLINE STATION	P.I. TO P.I. DATA	DELTA	RADIUS	CURVE DATA LENGTH	TANGENT	LONG CHORD	
10+00.00 (BEGIN)								
10	P.C. 10+01.49	S84°40'01"E 52.02ft.						
	P.T. 10+99.38		35°03'22"L	160.00 ft.	97.89 ft.	50.53 ft.	96.38 ft.	
	P.C. 11+35.92	N60°16'37"E 162.36 ft.	20°19'33"L	420.00 ft.	149.00 ft.	75.29 ft.	148.22 ft.	
20	P.T. 12+84.92							
	P.C. 13+85.52	N39°57'04"E 277.20 ft.	19°57'07"R	575.00 ft.	200.56 ft.	101.31 ft.	199.55 ft.	
30	P.T. 15+86.08							
	17+41.28 (END OF SURVEY)	N59°56'11"E 256.51 ft.						

**NARRATIVE OF SURVEY**

THIS SURVEY WAS PERFORMED WITH A ZEISS TH-43 THEODOLITE AND A K&E AUTORANGER EDM. PURPOSE OF THIS SURVEY IS TO CREATE PARCELS A AND B WITH THE INTENT TO EXCHANGE OWNERSHIP OF SAID PARCELS UNDER THE PROVISIONS OF THE SMALL TRACTS ACT OF JANUARY 12, 1983 (96 STAT. 2535, 16 U.S.C. 521C.)

**HISTORY OF SURVEYS**

THE EXTERIOR CORNERS OF SECTION 32 WERE ORIGINALLY ESTABLISHED BY FRANK W. CAMPBELL IN 1881 UNDER HIS G.L.O. CONTRACT NO. 380. SECTION 32 WAS SUBDIVIDED AND A PORTION OF STATE ROUTE 395 RIGHT-OF-WAY WAS ESTABLISHED AND MONUMENTED BY BAGETT, PLS 598, IN APRIL 1973. THIS PLAT ALSO ROUGHLY SHOWS THE LOCATION OF GRANT COUNTY ROAD NO. 21 SEE GRANT COUNTY SURVEY NUMBER 300. SECTION 32 WAS FURTHER SUBDIVIDED BY BISHOP, PLS 896, IN DECEMBER, 1980. SEE GRANT COUNTY SURVEY NUMBER 649.

- LEGEND**
- ( ) RECORD PER PLS 598
  - [ ] RECORD PER PLS 896
  - ⊗ FOUND - 2 1/2" IRON PIPE WITH 2 1/2" BRASS CAP SET BY LARRY D. BISHOP, PLS 896, IN 1980.
  - ⊗ FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP SET BY ROBERT D. BAGETT, PLS 598, IN 1973.
  - ⊙ SET 5/8" IRON ROD WITH 1 1/2" ALUMINUM CAP MARKED "USDA - FOREST SERVICE PLS 1636".
  - ⊙ SET 2 1/2" IRON PIPE WITH 2 1/2" BRASS CAP MARKED "1985 PLS 1636".
  - PARCEL CORNER - NOT MONUMENTED.
  - △ POINT OF INTERSECTION - CENTERLINE OF COUNTY ROAD NUMBER 21.
  - ⊙ POINT OF CURVATURE OR POINT OF TANGENCY, CENTERLINE OF COUNTY ROAD NUMBER 21.
  - ⊙ POWER POLE

**SURVEYOR'S CERTIFICATION**

I DENNIS L. GAYLORD, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY THIS PLAT, AND THE NOTES HEREON, ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER MY DIRECT SUPERVISION DURING JULY AND SEPTEMBER, 1985 FOR JOHN WEAKLAND AND THE U.S. FOREST SERVICE IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON.

**RECEIVED AND FILED**  
NOV 25 1985  
OFFICE OF COUNTY SURVEYOR  
Attest: *[Signature]*

*[Signature: Dennis L. Gaylord]*  
DENNIS L. GAYLORD P.S. 1636

REGISTERED PROFESSIONAL LAND SURVEYOR  
*[Signature: Dennis L. Gaylord]*  
OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

**PLAT OF SURVEY**  
LOCATED IN  
SECTION 32, T 7 S, R 31 E, W.M.  
U.S. DEPARTMENT OF AGRICULTURE  
UMATILLA NATIONAL FOREST  
GRANT COUNTY, OREGON  
DRAWN: *[Signature]* DATE: 11-13-85