

MAG. DEC.= 20° EAST



LEGEND

- ## HISTORY

In 1981, David B. Armstrong, Professional Land Surveyor, Oregon Reg. No. 1026, retraced and re-established the Range Line between Ranges 28 29 East and Ranges 14 15 Sec. Cor. Sec. 25/30 and the corner to Sections 16/7/12, while performing a Survey for the subdivision of Sections 18 & 19, Township 10 South, Range 29 East. That Survey was performed for the Malheur National Forest, under Contract No. 53-04H1-1-8448N and is on file in the Office of the Grant County Surveyor. (See Map of Survey 698)

I, Douglas M. Ferguson, Registered Professional Land Surveyor in the State of Oregon, hereby certify that this plat, notes and records hereon, or attached are a correct representation of the survey I performed during, May through Dec. 1985, with drafting & documentation performed Jan. 8 Feb. 1986, for the U.S. Forest Service, in accordance with the statutes of the State of Oregon and the articles of my contract No. 53-04H1-4-9684N.

Douglas M. Ferguson, Or. PLS 848

See standard U.S.F.S. "INDEX NO.", in the circle below and on sheet 2, and in corresponding circle on the Map above, and on sheet 2. Refer to "CERTIFIED RECORD OF LAND CORNER MONUMENTATION" forms which are a major part of the NARRATIVE of this survey and on file in the office of the Grant County Surveyor. Those forms give complete details as to the history, (both recorded & unrecorded) pertaining to these corners, as well as complete information as to the evidence found, the method of establishment, description of monuments set & accessories established. Monumentation basically consists of the following: Aluminum monuments, as shown in the LEGEND are stamped as shown below. Bearing Trees & other accessories are established as shown below, with Bearing Trees & other accessories being marked with white paint. Warning signs nailed on the back, brass washers stamped PLS 48 nailed on the blaze above the BT scribbling & painted a 6 red band around each tree. Set with warning and boundary signs on the property line, approx. 5 ft. each way from property corners & within 5 ft. in a cardinal direction from controlling corners.

TIOS R28E
LINE TREE
L7 SH/S13 2-1/2" dia, 30' aluminum pipe, with 3-1/2" aluminum cap, stamped on shown on the diagram, SET 26 in the ground, bears NO 18W, 7.4ft, from center of Line Tree " for reference monument to the line line.
P13 1985 Pine 5" dia, bears N59W, 11.1ft, from [m, scribbled] LINE TREE ST
RM 1985 Fir 14" dia, bears S83-W2E, 4.72ft, " LINE TREE BT
(Bearing Trees Reference center of Line Tree.)

TIOS R28E
S16
S14
S15
PLS 848
Pine 6" dia, bears N45E", 8.5ft., scribbled: SE 1/6 S14 BT
Pine 7" dia, bears S79W", 14.0ft., scribbled: SE 1/6 S14 BT

TIOS R28E
S16/S15
H-13 S22E132
1985
PLS 848
Fir 18" dia, bears N 59W, 13.9ft., scribbled: TIOS R28E S16 BT
Fir 10" dia, bears N29P, 3.10ft., scribbled: TIOS R28E S15 BT
Fir 12" dia, bears S28PE, 9.0ft., " TIOS R28E S22BT
Fir 22" dia, bears S4PW, 20.2ft, " TIOS R28E S21 BT

TIOS R28E
S15
H-15 S22E132
1985
PLS 848
Pine 14" dia, bears N36E", 33.4ft., scribbled: 1/4 S15 BT
Pine, the previously unrecorded tree which was scribbled approx. 75years ago, 4" dia, bears S 39E, 14.4ft., re-scribbled: 1/4 S22BT

TIOS R28E
S16/S14
H-17 S22E132
1985
PLS 848
Fir 10" dia, bears N30W, 37.6ft., scribbled: TIOS R28E S15 BT
Pine 6" dia, bears N59E, 32.1ft, " S14 BT
Fir 12" dia, bears S27E, 37.3ft, " TIOS R28E S23BT
s/s iron pin with plastic cap stamped "SURVEY MARKER PLS 848" of steel fence post with S4W warning signs alongside, bears S4PW, 10.0ft

(SEE SHEET 2 OF 2, FOR CONTINUATION
OF "MONUMENTATION")

(SEE SHEET 2 OF 2, FOR CONTINUATION
OF "MONUMENTATION")

RECEIVED AND
FILED
JUN 20 1986

OFFICE OF COUNTY SURVEYOR
Robert J. Bayola
Attest: *[Signature]*

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848