



**BASIS OF BEARINGS**  
SOLAR OBSERVATION

**LEGEND**

- Found Grant County Surveyor Brass Cap
- Found 5/8" iron pin of record
- Set 5/8" x 30" iron pin with attached yellow plastic cap marked B-G-A SURVEY MARKER.
- Point of Intersection

**REFERENCES**

Record Map of Survey No. 241		
Grant County Corner Remanumentation Records		
Commissioners Journal's	B - 268	
	B - 616	
	C - 310	
Deed Records Book 46 Page 527		
82	566	
89	466	
90	74	
95	574	
97	347	
107	111	
108	355-358	
109	865	
119	509-510	
121	457-459	
123	35-36	
130	320-321	

**NARRATIVE:** This survey was performed at the request of Marshall Gilmore, acting in behalf of the Grant County Court and Road Department. The purpose was to locate the existing road from Highway 26 near the southeast corner of section 19, T13S, R30E, W.M. for about 1.6 miles, then to locate an existing road through the Shirley Lee property which departed substantially from the old alignment through said property, then to locate a new alignment through Homer Harrison's property as approved by him and the roadmaster. A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments and appurtenant portions of the existing road. New monuments were set in accordance with the evidence found where appurtenant and at 30 feet on each side of the appropriate selected centerline of said road. The east line of section 19 was held for the west right of way line of the road until the road turned across the section line, this was in accordance with Deeds Book 46, Page 527. See "References" for a list of documents concerning this road.

VERN & MARILYN RANDALL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
  
ROBERT D. BAGETT  
JULY 12, 1943  
OREGON  
ROBERT D. BAGETT  
598

SHEET 1 OF 5

RECEIVED AND  
FILED  
AUG 18 1986  
OFFICE OF COUNTY SURVEYOR  
Robert D. Baggett  
Attest: *[Signature]*

BAGETT, GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY OF A PORTION OF COUNTY ROAD NO. 46 SITUATED IN SW 1/4 SW 1/4 SEC. 20, S 1/2 SEC. 19, T13S, R30E, B SEC. 24, SE 1/4 SEC. 23, NW 1/4 NE 1/4 SEC. 26, T13S, R29E, W.M. GRANT COUNTY OREGON		
SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT	
SURVEYED BY	R.D.B. & J.L.W. & M.D.B.	Mar-July '86
Scale: 1"=100'	Drawn by: J.L.W.	July '86