



LEGEND

- Found iron pipe with attached L.C. Stratton brass cap.
- Found iron pipe with attached BLM brass cap
- Found 2" iron pipe brass cap removed
- Set 5/8" x 30" iron pin with attached yellow plastic cap marked B-G-A SURVEY MARKER.
- Record bearing and distance
- Offset distance from \odot road to iron pin

REFERENCES

Record Map of Survey No. 67
BLM survey notes
Deed Records Book 86 Page 41-44
128 919-920

NOTE: Dimensions shown at offset pins are to \odot not to the offset pin.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
JULY 12, 1943
ROBERT D. BAGGETT
598

RECEIVED AND
FILED
SEP 3 1986

OFFICE OF COUNTY SURVEYOR
Robert D. Baggett
Attest: J. L. W.

BAGETT, GRIFFITH & ASSOCIATES
John Day, Oregon

MAP OF SURVEY
OF TWO TRACTS OF LAND SITUATED IN THE
N1/2SW1/4 SEC. 14, N1/2S1/2, SW1/4SW1/4 OF
SEC. 15, AND SE1/4 SE1/4 SEC. 16, T16S, R26E, W.M.

GRANT COUNTY OREGON

SURVEYED FOR	JIM SHIELDS
SURVEYED BY	R.D.B. & J.L.W. & M.D.B. 5/29/86 & 8/19/86
Scale: 1" = 500'	Drawn by: J.L.W. 8/14/86

RECORD MAP OF SURVEY NO. 948

NARRATIVE: This survey was performed at the request of Jim Shields. The purpose of this survey was to locate existing monuments, locate a portion of the Sunflower Creek Road, and determine the east line of the westerly 90 acres. A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments. New monuments were set in accordance with the evidence found. The BLM had set the section, 1/4 section, and exterior 1/16 corners pertaining to sections 14, 15, and 16 in 1960. In 1962 L.C. Stratton, P.E. No. 4563, subdivided these sections and monumented the 1/16 corners along the National Forest Boundary for the Ochoco National Forest as shown on Record Map of Survey No. 67. For the purpose of this survey I retraced portions of the exterior and interior lines of the sections as shown. I did not retrace the section boundaries or resubdivide the sections. In our survey we found all of the record monuments pertaining to this survey. Our survey disclosed that Stratton's iron pipe monumenting the center south 1/16 corner of section 14 is apparently 13 feet to the south of his record position. I did not tie the south 1/4 corner of section 14 in this survey. Mr. Shields is aware of the position of this monument. The northerly boundary of Mr. Shields property in the N1/2SW1/4, and SW1/4SW1/4 of section 15, and the SE1/4SE1/4 of section 16, is described along the Sunflower Creek Road. We located the centerline of the existing road. The area shown hereon is calculated to the center of the existing road as located.