

BASIS OF BEARINGS
SOLAR OBSERVATION

MERLE MORRIS
NW 1/4 SW 1/4

CECIL SWAGGART
N 1/2 SE 1/4

DATA
A=19°43'23"
R=520.00
L=179.00
LC=178.12
N 79°39'32"E

Q station 29+87.50 is 1381.37 feet north
and 245.28 feet east of the SE corner
of section 5. Said corner is monumented with
a Grant County Surveyor Brass Cap.

MERLE MORRIS
SW 1/4 SW 1/4
SEC. 5 SEC. 4

MERLE MORRIS

SW 1/2 SE 1/4

LEGEND
● Found original corner evidence
Set Grant County Surveyor 3" brass disc
on a 3" stem grouted in bedrock.
○ Set 5/8" x 30" iron pin with attached yellow
plastic cap marked B-G-A SURVEY MARKER
x—x Fence line

NOTE: Section and section subdivisional
lines shown are protracted from the found
section corners at the NW corner of
section 3 and the SW corner of section
4. The lines protracted are for general
information only.

REFERENCES

Record Map of Survey No. 154
Deed Records Book 87 Page 495
87 497
104 64
124 641
131 205-206
132 748-756
133 976-977
110 539
Leases & Agreements Book 'I' Page 400
'L' 722-723
GLO Survey Notes

NARRATIVE: This survey was performed at the request of Marshall Gilmore,
attorney, acting in behalf of the Grant County Court. The purpose of this
survey was to locate a portion of the existing road from station 0+00 to
station 110+00. We also located a new alignment from station 110+00 to
station 139+61.31. We also located a more suitable location through a portion of
William Rehders property. This portion was relocated at the request of Mr.
Rehder to keep the road out of a creek and out of his farmed field.
This relocation was approved by A.C. Bond, roadmaster, and the County Court.
A search was made of the available records pertaining to this survey. Field
measurements were made to locate the centerline of the existing road from
station 0+00 to station 110+00. New monuments were set 30 feet each side
of said centerline as shown. Field measurements were made to locate the cen-
terline of the new alignment portion from station 110+00 to station 139+61.31.
New monuments were set 30 feet each side of this centerline as shown. We
also made field measurements to locate appropriate section corners as indi-
cated herein.
I found no unusual conditions with this survey. See "References" for a list of
documents concerning this road. For a detailed explanation of corner evidence
found and bearing tree information see corner restoration sheets filed in the
Corner Restoration Book.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
ROBERT D. BAGETT
598

SHEET 1 OF 5

BAGETT, GRIFFITH & ASSOCIATES
John Day, Oregon

MAP OF SURVEY
OF COUNTY ROAD NO. 22 SITUATED WITHIN THE
N 1/2 SW 1/4 N 1/2 SEC. 3,
SW 1/2 SEC. 4, S 1/2 SEC. 5, T 8 S, R 30 E, W. M.

GRANT COUNTY, OREGON

SURVEYED FOR GRANT COUNTY ROAD DEPARTMENT

SURVEYED BY R.D.B. & J.L.W. & M.D.B. Oct.-Dec. '86

Scale: 1"=100' Drawn by: J.L.W. Nov. '86