

529

CAMPBELL RECORD

SE 1/4 PRIVATE

SW 1/4 MALHEUR N.F.

LEGEND

- MONUMENT SET
- A.P.M. 2 1/2" X 30" LONG ALUMINUM PIPE WITH 3" ALUMINUM CAP
- /// POSTED LINE
- B.T. BEARING TREE
- M.O.S. MOUND OF STONE
- P.P. PONDEROSA PINE
- D.F. DOUGLAS FIR
- DEP.O.S. DEPOSITED ORIGINAL STONE
- x-x-x WIRE FENCE LINE
- (N-13) CORNER INDEX NUMBER

SURVEY NOTES

BEARINGS ARE BASED ON SOLAR OBSERVATION AT A POINT 550' N. OF SECTION CORNER. ALL BEARING TREES AND MONUMENTS MARKED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER STAMPED "AS&E LS 1026" NAILED TO BLAZE FACE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED. DISTANCES TO CENTER OF TREE MARKED BY NAIL IN SIDE OF BT. SEE ALSO ACCOMPANYING CORNER RECORD FORMS FOR ALL CORNERS AND ATTACHED SURVEY NARRATIVE.

HISTORY

THE CORNER COMMON TO SECTIONS 15, 16, 21 AND 22 WAS ESTABLISHED BY SAMUEL W. LACKLAND UNDER G.L.O. CONTRACT NO. 415 IN 1881. THE LINE BETWEEN SECTIONS 15 AND 16 WAS SURVEYED BY WILLIAM E. CAMPBELL UNDER G.L.O. CONTRACT NO. 652 IN 1896.

CAP MARKED:

T145R27E
1/4
S16 | S15
LS 1026
1986

FND: BASALT STONE 24" X 10" X 6" SET IN 3' M.O.S. MARKED "1/4" ON E. FACE. ORIGINAL B.T.'S: A 26" P.P., S. 72 3/4° E., 41.4-HEALED FACE; A 21" JUNIPER, S. 48 1/4° W., 83.5-VISIBLE SCRIBING-145 B. SET: A.P.M. 20" IN GRND. IN 3' M.O.S., DEP. O.S. SOUTH.

FND: 28" PONDEROSA PINE WITH HEALED NOTCHES N. AND S. FACES, TREE REMARKED ABOUT 25± YEARS AGO.

B.T.'S MARKED:

8" P.P., N. 26 1/4° E., 57.3, SCRIBED-AP S15 BT; 9" P.P., N. 76 1/4° W., 28.8, SCRIBED-AP S16 BT.

FND: BASALT STONE 17" X 14" X 12" SET 8" IN GRND. MARKED 3 GROOVES ON S. & E. FACES WITH 3' M.O.S. CENTERED 4' WEST.

SET: A.P.M. 15" IN GRND. IN 3' M.O.S., DEP. O.S. SOUTH.

B.T.'S MARKED:

8" P.P., N. 8 1/2° E., 26.5, SCRIBED-T145R27E S15 BT; 9" D.F., S. 87° E., 23.8, SCRIBED-T145R27E S22 BT; 11" P.P., S. 25° W., 27.3, SCRIBED-T145R27E S21 BT; 14" D.F., N 38 1/2° W., 23.2, SCRIBED-T145R27E S16 BT.

SCALE

1" = 500'

FEET

0 500

250

REGISTERED PROFESSIONAL LAND SURVEYOR

David B. Armstrong

12/5/86 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

RECORDATION

OFFICE OF COUNTY SURVEYOR,
COUNTY OF GRANT,
STATE OF OREGON.

I HEREBY CERTIFY THAT THE WITHIN INSTRUMENT WAS RECORDED JAN 12, 1987.

C.S. NO. 973

Robert D. Ray
COUNTY SURVEYOR

SURVEY OF MALHEUR NATIONAL FOREST BOUNDARY LINE BETWEEN SECTIONS 15 AND 16, T. 14S., R. 27E., W.M., GRANT COUNTY, OREGON

SHAKE CADASTRAL SURVEY

CONTRACT NO. 53-04H1-6-0172 N

SURVEYED ~ OCTOBER, 1986

FIELD BOOKS 1 & 2

W.O. 86-529 ~ A

SURVEYOR'S CERTIFICATION

I, DAVID B. ARMSTRONG, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY THAT THIS PLAT AND THE NOTES HEREON, OR ATTACHED, ARE A CORRECT REPRESENTATION OF A SURVEY I PERFORMED IN OCTOBER, 1986, AT THE REQUEST OF THE U.S.D.A., FOREST SERVICE, IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON, AND THE ARTICLES OF MY CONTRACT.

SURVEY FOR

MALHEUR NATIONAL FOREST
139 N.E. DAYTON STREET
JOHN DAY, OREGON 97845

SURVEY BY

ARMSTRONG SURVEYING & ENG., INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503 5447-7791

MO5 No. 973