



NARRATIVE: This survey was performed at the request of Steve Holmes, acting in behalf of Avis Holmes. The purpose of this survey was to locate the tract of land shown hereon lying between the river and the Deer Creek County Road. A search was made of the available records pertaining to this survey. Field measurements were made to locate the NE corner of section 32, applicable portions of the county road and river. New monuments were set at locations approved by Mr. Holmes as shown hereon. A search was made for the original $\frac{1}{4}$ corner on the south boundary of section 32, set by Aaron York in 1879. Although I found a rock of call size with several large rocks scattered near it, I could not positively identify marks on the stone. I also searched for the south $\frac{1}{4}$ corner of section 32 set by Henry Meldrum in 1881, but found no evidence. I then searched for the original SE corner of section 32 as set by York, but I did not find this stone either. Consequently, I can not yet accept the first stone mentioned until I find additional corner evidence to the east along this township line. I abandoned further search during this survey in the interest of economy. I did not determine the location of the township line for the reason stated above.

BASIS OF BEARINGS SOLAR OBSERVATION

LEGEND

- Set $\frac{5}{8}$ "x30" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.
- x—x Fence

REFERENCES

Original GLO Survey Notes.
Survey No. 863
Section Corner Remonumentation Records
Deeds: Book 85 Page 36, Book 133 Page 920-927

SEC. 32, T8S, R28E

Township Line not established this survey. See narrative.

SEC. 6, T9S, R28E

RECEIVED AND
FILED

OCT 7 1987

OFFICE OF COUNTY SURVEYOR
Attest: *Robert D. Bagett*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Bagett
OREGON
JULY 12, 1983
ROBERT D. BAGETT
598

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY OF A TRACT OF LAND SITUATED IN THE SW $\frac{1}{4}$ SECTION 32 T8S, R28E, W.M. GRANT COUNTY, OREGON		
SURVEYED FOR	AVIS HOLMES	
SURVEYED BY	R.D.B., D.I.G., & M.W.P.	3&5/87
Scale: 1" = 100'	Drawn by: M.W.P.	10/2/87