


CORNER RESTORATION

CORNER: C1/4 Cor. Sec. 11, Twp. 14 S., Range 30 E., W.M.

ORIGINAL SURVEY BY: CORNER

SURVEY NUMBER: NOT PREVIOUSLY

CONTRACT DATE: ESTABLISHED




ORIGINAL G.L.O. DESCRIPTION: Corner not previously established

EVIDENCE FOUND: None, corner not previously established. The corner point falls about 6 feet north of an East-West fence line.

At the corner point, I set a 5/8"x15" iron pin 15" in the ground, driven to bedrock, with attached 2" aluminum cap marked as shown below. I built a 2 foot mound of stone around the monument and placed a 4 ft. steel fence post alongside the mound of stone.

FROM WHICH, I set the following reference points:

- a 5/8"x10" iron pin, driven to bedrock, bears N.40°11'E., 19.44 feet with attached yellow plastic cap marked BENCHMARK SURVEYING;
- a 5/8"x10" iron pin, driven to bedrock, bears S.43°28'E., 22.88 feet with attached yellow plastic cap marked BENCHMARK SURVEYING;
- a 5/8"x30" iron pin bears S.27°15'W., 29.40 feet with attached yellow plastic cap marked BENCHMARK SURVEYING;
- a 5/8"x15" iron pin, driven to bedrock, bears N.38°12'W., 17.80 feet with attached yellow plastic cap marked BENCHMARK SURVEYING;



Bearings are based on Record Map of Survey No. 1989.

RESTORATION BY, STAMP AND DATE:

Michael C. Springer, PLS
Benchmark Land Surveying, Inc.
217 N. Canyon Blvd.
John Day, OR 97845

March 4, 2014

RECEIVED AND FILED
GRANT COUNTY SURVEYOR

MAR 7 2014

BY 

REGISTERED
PROFESSIONAL
LAND SURVEYOR


OREGON
JULY 8, 2002
MICHAEL C. SPRINGER
#70918

EXPIRES: 6/30/2014