

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. H-12

History of original corner establishment:

Grant County Survey Records show no previous establishment of this Cor.

DIAGRAM

T14S R35E
SE 1/16
S 9
1987
RLS 848

Description of corner evidence found:

Grant County Survey Records show no previous establishment of this Cor.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 26" in the ground.



From Which:

A Fir 14" dia., Bears N85°W., 43.8 ft., scribed: SE 1/16 S9 BT

A Fir 10" dia., Bears N84°E., 34.8 ft., scribed: SE 1/16 S9 BT

Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.

Nailed a brass washer stamped RLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, South & West 4 ft. from the corner.



This work is performed by:
Douglas M. Ferguson RLS 848
Mt. Vernon Oregon.
On: July 7, 1987
Refer to Map of Survey No. 1009

Office of Surveyor County of Grant
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 6 day of Nov, 1987
Robert A. Bunch by _____
(COUNTY OFFICIAL) (DEPUTY)