

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner has not been previously set.

DIAGRAM

T14S R35E

S31
SWSESE
1/256

1991
PLS 699

Description of corner evidence found:

Corner is being set by this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2"x30" aluminum pipe with a 2½" aluminum cap, marked as shown in the diagram, 28" in the ground, at a point as determined by the procedures set forth in the MANUAL OF INSTRUCTIONS FOR THE SURVEY OF PUBLIC LANDS for the subdivision of sections. Built a mound of rock to be 36" in diameter by 4" high around the monument, from which new BTs are:

12" Western larch bears N37°45'W, 18.5 feet scribed SWSESE1/256 S31 BT

14" Englemann spruce bears S74°45'W, 8.5 feet scribed SWSESE1/256 S31 BT

Attached BT and a Land Survey Monument signs to and painted a red band around each BT. Bearings were turned from the control traverse with a theodolite, basis of bearing being a solar observation that was made on the adjacent McCoy Cadastral Survey contract in 1987, to stamped brass washers nailed on new BTs in the scribed red-painted blazes or to the red-painted blazes or scars on old BTs. Distances were measured from a 60d spike, with an aluminum washer stamped PLS 699, which was driven into the side of each BT approximately one foot above the ground.

Set steel fence posts 4.8 feet S and 7.5 feet W of the corner on the National Forest boundary lines. Attached Forest Boundary signs to each post and a Land Survey Monument sign to the S post.



I, Leland L. Myers, 587 E. Auburn St., P.O. Box 98, Sumpter, OR 97877, do hereby certify that on October 5, 1991, I established the corner as herein described.

FILED

IN THE OFFICE OF THE Grant COUNTY SURVEYOR

THIS 30 DAY OF NOV, 19 92

Robert D. Beyer
Grant County Surveyor



MAP OF SURVEY No. 1197