


RECORD OF LAND CORNER MONUMENTATION

CORNER: S1/16 Cor. Sec. 17, Twp.9S., R.26E., W.M.

ORIGINAL SURVEY BY: CORNER

CONTRACT NUMBER: NOT PREVIOUSLY

CONTRACT DATE: ESTABLISHED



ORIGINAL G.L.O. DESCRIPTION: N/A, Corner not previously established.


EVIDENCE FOUND: N/A, Corner not previously established.

DESCRIPTION OF MONUMENT AND ACCESSORIES SET: At the midpoint between the E1/4 Corner and the Southeast Corner of Section 17, I set a 5/8" x 15" iron rod, driven to bedrock, with attached 2" aluminum cap marked as shown below. I built a 1 ft. mound of stone around the new monument.

FROM WHICH, I set the following reference points:

A 5/8"x15" iron pin, driven to bedrock, bears S.64°28'W., 11.08 ft., with attached yellow plastic cap marked BENCHMARK SURVEYING

A 5/8"x30" iron pin, bears N.40°32'W., 11.16 ft., with attached yellow plastic cap marked BENCHMARK SURVEYING.



Bearings shown hereon to reference points are based on Record Map of Survey No. 2027.


RESTORATION BY:

Michael C. Springer, PLS
Benchmark Land Surveying
217 N. Canyon Blvd.
John Day, OR 97845

April 18, 2015

RECEIVED AND FILED
GRANT COUNTY SURVEYOR

APR 24 2015

BY: 

REGISTERED
PROFESSIONAL
LAND SURVEYOR


OREGON
JULY 9, 2002
MICHAEL C. SPRINGER
#70918

EXPIRES: 6/30/2016