


CORNER RECORDS: ALL CORNERS ARE MONUMENTED WITH 2 1/2" ϕ X 30" LONG ALUM. MON. STAMPED AS SHOWN. A STEEL F. POST IS ADJACENT TO EACH CORNER WITH "SURVEY MONUMENT" AND "FOREST BOUNDARY" SIGNS ATTACHED

ALL BEARING TREES HAVE A 6" BAND OF RED PAINT, "BEARING TREE" AND "SURVEY MONUMENTS" SIGNS AND A BRASS WASHER STAMPED "PLS 1288" SET AT THE BASE.

TRACT #1 S.T.A. NO. 060401


AP #2



REFERENCE POINTS:

BRASS CAP - NW 1/4, S36, BEARS N 89°52'55"E, 45.00 FT.
ALUM. CAP - AP #3, TR 1, BEARS S 00°07'05"E, 300.00 FT.

AP #3



REFERENCE POINTS:

14" ϕ L.P. PINE BEARS N 42°15'W, 45.7 FT. SCRIBED "AP 3 TR 1"
12" ϕ L.P. PINE BEARS S 56°15'W, 40.4 FT. SCRIBED "AP 3 TR 1"

AP #4



REFERENCE POINTS:

BRASS CAP - NW 1/4, S36, BEARS N 00°07'05"W 300.00 FT.
ALUM. CAP - AP #3, TR 1, BEARS S 89°52'55"W, 45.00 FT.

TRACT #2 S.T.A. NO. 402


AP #1



REFERENCE POINTS:

ALUM. CAP - AP #2, TR 2, BEARS S 89°53'30"E, 40.00 FT.
ALUM. CAP - AP #4, TR 2, BEARS S 00°06'30"W, 150.00 FT.


AP #2



REFERENCE POINTS:

6" ϕ L.P. PINE BEARS N 70°30'E, 9.0 FT. SCRIBED "AP 2, TR 2"
4" ϕ L.P. PINE BEARS S 29°00'E, 10.9 FT. SCRIBED "X"


AP #3



REFERENCE POINTS:

8" ϕ L.P. PINE BEARS N 15°20'E, 82.6 FT. SCRIBED "AP 3, TR 2"
8" ϕ L.P. PINE BEARS S 66°45'E, 58.2 FT. SCRIBED "AP 3 TR 2"

AP #4



REFERENCE POINTS:

ALUM. CAP - AP #3, TR 2, BEARS S 89°53'30"E 40.00 FT.
ALUM. CAP - AP #1, TR 2, BEARS N 00°06'30"E, 150.00 FT.

CERTIFICATION:

I, CHRIS T. PALMER, LAND SURVEYOR REGISTERED IN ACCORDANCE WITH THE LAWS OF THE STATE OF OREGON, HEREBY CERTIFY THAT THIS PLAT HEREON IS A TRUE REPRESENTATION OF A SURVEY I PERFORMED UNDER THE "SMALL TRACTS ACT" AT THE REQUEST OF TOM CLEMENS IN DECEMBER OF 1989 IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON.

Chris T. Palmer

CHRIS T. PALMER, P.L.S.
OREGON LICENCE NO. 1288

APPROVAL:

EXAMINED AND ACCEPTED FOR THE MALHEUR NATIONAL FOREST THIS _____ DAY OF _____.

TITLE: _____

RECORDATION:

OFFICE OF THE GRANT COUNTY SURVEYOR, STATE OF OREGON. I HEREBY CERTIFY THAT THE WITHIN INSTRUMENT WAS FILED FOR RECORD ON THIS 13 DAY OF Feb, 1990

COUNTY SURVEY NO. 1128

Robert D. Sayre
GRANT COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR <i>Chris T. Palmer</i> OREGON SEPTEMBER 23, 1977 CHRIS T. PALMER 1288	TOM CLEMENS		BURNS, OR.	
	SURVEY PLAT OF SMALL TRACTS ACTS SURVEY NO'S 060401 AND 060402 IN SECTIONS 26 AND 36, T18S, R30E, WM. GRANT CO. OR.			
	Scale: —	Date: DEC 1989	Job: 1193	
	Dsn: —	M. A. PALMER & SONS, INC. ENGINEERING & SURVEYING 254 N. Alder - Box 61 Burns, Oregon 97720		Sht. No. 2
	Drn: CTP	Ckd: CTP	of 2	