



**LEGEND**

- Found 1/2" iron pipe with attached Grant County Surveyor brass cap. See Survey No. 502.
- Set 5/8"x30" iron pin with attached red plastic cap, marked CORNERSTONE SURVEYING, INC
- X—X Fence line

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Jack L. Watson*  
OREGON  
SEPT. 19, 1985  
JACK L. WATSON  
2734  
Renewal Date 6/30/2008

**NARRATIVE**

This survey was performed at the request of Ken Holliday, on behalf of Holliday Family Ranch, Inc. The purpose of this survey was to survey and describe the proposed boundary agreement lines as shown.

This survey was performed using static GPS receivers and Electronic Total Station. The bearings for this survey are based on the GPS survey. The GPS survey was made in NAD 83 state plane coordinates, Oregon north zone. The state plane bearings were rotated clockwise 01°11'25" to true north near the SE corner of Section 14, T13S, R32E. All bearings are relative to this local north meridian.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the monuments shown, the fence lines to be used for the new boundaries and to establish the new corner monuments.

RECEIVED AND  
FILED  
Aug 4, 2006

OFFICE OF COUNTY SURVEYOR  
*Jack L. Watson*

See Sheet 2

**CORNERSTONE SURVEYING, Inc.**  
233 S. Canyon Blvd., John Day, Oregon 97845  
(541) 575-1813

MAP OF SURVEY  
PROPOSED BOUNDARY AGREEMENT LINES  
SECTION 14, 24, 25 AND 36  
T13S, R32E, W.M.  
GRANT COUNTY, OREGON  
SURVEYED FOR: **HOLLIDAY FAMILY RANCH, INC.**  
SURVEYED BY: Jack Watson Date: May 2006  
DRAWN BY: Jack Watson